

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25832-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 11-29S-16E
1881 feet from S Section Line, 1989 feet from W Section Line
Lease Name: STREETS REVOCABLE TRUST Well #: 11-1
County: WILSON Total Vertical Depth: 1097 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	936		120 SX
SURF	8.625	21		6 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/21/2018 9:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 06/21/2018 9:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. A total of 84 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
639	643		
626	630		

RECEIVED
KCC DIST # 3
JUL 13 2018
CHANUTE, KS

AD

INVOICED

JUL 20 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)