

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23067-00-00
Spot: SENW Sec/Twnshp/Rge: 8-20S-11W
3400 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: PETERS Well Number: 1
County: BARTON Total Vertical Depth: 3309 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 4.5 feet: 3307 125 SX CMT
Surface Casing Size: 8.625 feet: 248 185 SX CMT

8 107.54

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2003 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 738-2943

Proposed
Plugging
Method:

Ordered out 190 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/21/2003 1:15 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3250' and topped with 5 sxs cement.
Cut casing off at 1610'.
Pulled up to 1300' - mixed and pumped 90 sxs cement with 300# hulls.
Pulled up to 500' - spotted 30 sxs cement with 100# hulls.
Pulled up to 250' and circulated cement with 70 sxs.
POOH. Hole full of cement.


RECEIVED
APR 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-24-03


INV. NO. 2003061450

APR 22 2003

RECEIVED

PETROELUM ENERGY, INC. #1 PETERS 8-20-11W
 415 FIRST NAT'L BANK BLDG. WICHITA, KS 67202 100'N.
 CONTR WHITE & ELLIS DRLG., INC. CTY BARTON C SE NW
 GEOL _____ FIELD CHASE-SILICA

ELV 1781 KB SPD 3/17/83 CARD ISSUED 4/28/83 IP P 63 BOPD, NW
 1776 GL ARB OH 3307-3309
 API 15-009-23,067



SMP	Topo	Depth/Datum
HEEB		2919-1138
TOR		2934-1153
DOUG		2952-1171
BR LM		3044-1263
LANS		3062-1281
ARB		3306-1525
RTD		3309-1528

8 5/8 " 248/185SX; 4 1/2 " 3307/125SX
 DST (1) 3268-3309 (ARB) / 30-30-30-30, REC 795' CO, 1020'
 SMC GSY OIL, NW, SIP 828-848#, FP 255-489 / 559-669#
 MICT - CO, (ARB OH), SWB 20 BOPH - NW, ONFU 3003' OIL -
 NW, POP, P 63 BOPD, 4/18/83

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS