

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23938-00-00
Spot: CSWSWNW, Sec/Twnshp/Rge: 8-20S-11W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: PETERS Well Number: 2
County: BARTON Total Vertical Depth: 3522 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 8100 E. 22ND N. BLDG. 300
WICHITA, KS 67226

Production Casing Size: 5.5 feet: 3352 150 SX CMT
Surface Casing Size: 8.625 feet: 260 200 SX CMT

\$114.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/18/2003 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Ordered out 190 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 04/18/2003 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3260' and topped with 5 sxs cement.
Shot off casing at 1700'.
Pulled up to 1300' and mixed and pumped 90 sxs cement with 300# hulls.
Pulled up to 500' and spotted 30 sxs cement with 100# hulls.
Pulled up to 250' and circulated cement with 50 sxs cement.
POOH. Hole full of cement.

RECEIVED
APR 23 2003
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

[Handwritten Signature]

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-24-03

INV. NO. 2003061450

APR 21 2003

PETROLEUM ENERGY, INC. 8-20-11W
 224 F. DOUGLAS, #350 #2 PETERS SW SW NW
 WICHITA, KS. 67202
 CONTR. BIG SPRINGS DRILLING CTY. BARTON
 GEOL. TODD SEYMOUR FIELD CHASE-SILICA
 ELV. 1785 KB SPD. 5/9/85 CARD ISSUED 6/20/85 IP. P 72 BOPD
 1779 GL. ARB 3316-3318

+	+	+
+	+	+
+	+	+

SMP	Tops	Depth/Datum	API 15-009-23,938
HEEB	2922-1137		8 5/8 " 260 / 200SX, 5 1/2 " 3352 / 150SX
TOR	2937-1152		DST (1) 3274-3306 (ARB) / 45-45-45-45, WB & DIED, REC 2' M, SIP 31-31#, FP 31-31 / 31-31#
DOUG	2952-1167		
BR LM	3045-1260		DST (2) 3274-3313 (ARB) / 45-45-45-45, WB, REC 55' OIL & GCM, SIP 1049-1049#, FP 41-41 / 41-41#
LANS	3063-1278		
ARB	3296-1511		DST (3) 3274-3323 (ARB) / 30-30-30-30, SB, REC 780' HVY OIL CMW (45% OIL), SIP 1132-1132#, FP 72-250 / 302-375#
FTD	3353-1568		MIGT - CO, PF (ARB) 3316-18, SWB DWN, REC 17 BOPH, NAT, POP, P 72 BOPD, NW, 6/10/85