

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-19043-00-01  
Spot: CN2SWNW Sec/Twnshp/Rge: 8-20S-11W  
3630 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: PETERS Well Number: 3  
County: BARTON Total Vertical Depth: 3662 feet  
Production Casing Size: 5.5 feet: 3386 175 SX CMT  
Surface Casing Size: 8.625 feet: 240

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

9/19.02

Well Type: SWD UIC Docket No: D25056.0 Date/Time to Plug: 04/22/2003 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed  
Plugging  
Method:

Ordered out 190 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 04/22/2003 1:30 PM KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Sanded back casing to 3200' and topped with 5 sxs cement.  
Casing parted at 930' - could not get back down the hole - decided to P&A.  
At 930' - mixed and pumped 120 sxs cement with 400# hulls.  
Pulled up to 250' and circulated cement with 60 sxs.  
POOH. Topped off with 10 sxs cement.


RECEIVED  
APR 28 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 4-29-03

INV. NO. 2003061465

APR 23 2003

IMAGED

VESS OIL CORPORATION  
WICHITA, KS. 67208

8-20 -11W  
C N/2 SW NW

#3 PETERS OWWO

site: 1-1/4 S OF ELLINWOOD, KS.		city: BARTON		API 15-009-01041	
contr: DUKE DRILLING, INC.		field: CHASE-SILICA			
geol:					
fr	spd	drig	card	last	
date 05/01/87	date 06/11/87	comp	issued 07/01/87	revised 07/01/87	

A	+	+
+	+	+
+	+	+

elv: 1784 KB SMP	
tops .....	depth/datum
ANH.....	520 +1264
HEEB.....	2930 -1146
LANS.....	3075 -1291
BKC.....	3313 -1529
ARB.....	3322 -1538
RTD OLD.....	3362 -1578
DDTD.....	3662 -1878

IP status:  
SWDW, ARB OH 3387-3662 ,

OLD INFO: OPERATOR WAS ALPINE OIL & REFINERY ,  
COMPANY 2 DUNCAN "B" SPD 10/05/46 , SET 8-5/8"  
239 D & A, ARB , (CARD ISSUED 10/17/46 )  
CONTR: UNKNOWN  
V SLI SO AT 3362  
NO CORES OR DST'S

NEW INFO: FR 05/01/87 , RE-ENTERED 06/11/87 WSH  
DWN TO 3362 CSG: DD 3662 TD, 5-1/2" 3387 DD 3662 TD,  
MICT - CO, (ARB OH), AC 1500, SWDW - INJECTION RATE  
SATISFACTORY