

1-3 15.009.14390.0000 *JL R*

To: **6 041248**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 2-11-40
N/2 NE SW, SEC. 8, T 20 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4813
Operator: Mustang Oil and Gas Corp
Name & Address Box 1609
Great Bend, Ks. 67530

2310 feet from S section line
3300 feet from E section line
Lease Name B. Howard Well # 1
County Barton 107.54
Well Total Depth 3309 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8 feet 234 w/160 sks

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address Great Bend, Ks.

Company to plug at: Hour: 9:00 AM Day: 3 Month: Jan Year: 19 91

Plugging proposal received from Raeford Clark

(company name) Mustang Oil and Gas Corp (phone) _____

were: 5 1/2 casing set at 3306 w/150 sks cement; O.H. to 3309; Perf anhy at 550;
Perf at 12'. Holes in casing at 2328; 1976; and 86'. top of fish at 3186. Ordered
350 sks 65/35 poz 10% gel w/1/2 lb f.c. plus 5 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00 pm Day: 3 Month: JAN Year: 19 91

ACTUAL PLUGGING REPORT R. I. H. w/tubing to 3115; Spt 100 sks cement w/

2 sks hulls; pull up tubing to 2100; Spt 100 sks cement w/2 sks hulls; pull up tubing to
1100; Circ cement to surf w/100 sks cement: pull tubing; hook up to 5 1/2 casing
sq. 100 add sks cement. Max 500 lbs. S.I. 100 lbs.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 13 1991

INV. NO. 30709
1-3

MAR 07 1991

Signed Dennis L. Hamel
(TECHNICIAN)
Dennis L. Hamel