

4-080194

32  
P

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-19 API number: 15.009.14555.0000

NE NW NE /4 SEC. 15, 20S, 11 W  
4950 feet from S section line  
1650 feet from E section line

Operator license# \_\_\_\_\_ Lease State Riverbed well # 2

Operator: Kansas Corporation Comm County Barton

Address: 2301 East 13th Well total depth 3283 feet  
Hays, Kansas 67601 Conductor Pipe: \_\_\_\_\_ inch @ \_\_\_\_\_ feet  
Mark Casebeer-defunct Surface pipe 8 5/8 inch @ 234 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Kincaid Well Service License# 7252

Address: P. O. Box 726, Ellinwood, Kansas

Company to plug at: Hour: PM Day: 19 Month: June Year: 1996

Plugging proposal received from: Herb Deines

Company: Kansas Corporation Commission phone: 913-628-1200

Were: 4 1/2" inch set at 3283'. Perfed at 1350'. Ran tubing to 2600'.  
Pumped 90 sx 60/40 poz, 10% gel and 200# hulls. Pulled tubing to 1400'.  
Pumped 35 sx 60/40 poz, 10% gel. Pulled tubing to 700'. Pumped 135 sx  
60/40 poz, 10% gel but did not circ cement. Ordered 150 sx 60/40 poz, 10%  
gel. Pulled tubing to 350'. Pumped 45 sx 60/40 poz, 10% gel. Pulled  
tubing. Pumped 35 sx 60/40 poz, 10% gel down 4 1/2" X 8 5/8" annulus and  
circ cement out of 4 1/2". Squeezed with 5 sx cement. Max 100#, SI 50#.

Plugging Proposal Received by: Bruce Basye

Plugging operations attended by agent? All[XXX], Part[ ], None[ ]

Completed: Hour: 7:20 PM, Day: 19, Month: June, Year: 1996

Actual plugging report: Plugged as described above.

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 24 1996

CONSERVATION DIVISION  
WICHITA, KS

Remarks: Allied cementing on location

Condition of casing(in hole): GOOD \_\_\_\_\_ BAD X Anhy. plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING X, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

I did[XX] / did not[ ] observe the plugging.

*Bruce D. Basye*  
Bruce D. Basye  
(agent)