

4-060373

12-22

872

15.009.14452.0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 7-40

CNL NW /4 SEC. 11, 20 S, 11 W
5250 feet from S section line
3960 feet from E section line

Operator license# 3613

Lease F. Panning well #D-21

Operator: Hallwood Petroleum, Inc.

County Barton

Address: P.O. Box 378111
Denver, CO 80232

Well total depth 3292 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 220 feet

106.99

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Kelso Casing Pullers, Inc. License# 6050

Address: P.O. Box 347 - Chase, Kansas 67524

Company to plug at: Hour: 8:30A.M. Day: 22 Month: December Year: 92

Plugging proposal received from: Mike Kelso

Company: Kelso Casing Pullers, Inc. Phone: 316-938-2943

Were: Order 250 sxs. 60/40 pozmix - 8% gel.
Plug thru casing.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:10P.M., Day: 22, Month: December, Year: 92

Actual plugging report: 8 5/8" to 220'. 5 1/2" to 3277'. Shot one
time and pulled 2022' of casing. Sanded back to 3225' and spotted
5 sxs. with bailer. Pulled casing to 1200' and loaded casing with
110 sxs. cement. Pulled casing to 600' and pumped 50 sxs. cement.
Pulled casing to 300' and circulated cement to surface with 80 sxs.
cement. Pulled casing and topped with 10 sxs. cement.

Remarks: Allied Cementing

Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO

Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO IAAI

Plugged through TUBING, CASING X. Elevation: 1760 GL

I did [X] / did not [] observe the plugging.

Signature of Herb Deines

RECEIVED STATE CORPORATION COMMISSION

5 1993

DATE 1-12-93

(agent)

INV. NO. 37190

Form CP-2/3

12-22-92