

To: 6 062478  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICKITA, KANSAS 67202

8-20 API NUMBER 15- 009-22.028.0000 275R

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

Operator: Hallwood Petroleum, Inc.  
Name & Address: 4582-S Ulster St. Pkry. #1700  
P.O. Box 378111  
Denver, Colorado 80237

SW, SEC. 11, T 20 S, R 11 WE  
1980 feet from S section line  
3960 feet from E section line

Lease Name Stueckenann Well # A-17

County Barton 106.50

Well Total Depth 3275' P.B. (3277') feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 508'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Hallwood Petroleum, Inc. License Number 3613

Address Box 404, Plainville, Kansas 67663

Company to plug at: Hour: 9:00A.M. Day: 20 Month: August Year: 19 91

Plugging proposal received from Aven Weverling

(company name) Hallwood Petroleum, Inc. (phone) 913-434-2351

were: Order 300 sks. of 60/40 posmix - 8% gel. - 5 sks. hulls.

Plugging Proposal Received by Gilbert G. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:30P.M. Day: 20 Month: August Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 508' w/275 sks. 5 1/2" set at 3274' w/100 sks.

Top perf. at 3275'. Plugged bottom with sand and 5 sks. cement to 3225'. Shot pipe 1 time and recovered 2500'. Pumped in 8 5/8" 25 sks. cement followed with 5 sks. hulls in 300 sks. cement w/600 P.S.I.

RECEIVED STATE CORPORATION COMMISSION

AUG 29 1991

Remarks: By: Halliburton. Ran Line to 3000'. DIVISION

(If additional description is necessary, use BACK of this form.) Kansas

INVOICED (I could not find the observe this plugging.)

DATE 9-11-91

Signed Gilbert G. Scheck (TECHNICIAN) E.O.S.

INV. NO. 33071