

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613  
Operator: Quinoco Petroleum Inc.  
Name &  
Address Box 278111  
Denver, Colorado 80237

X 11-30 15.009.14447.0001  
API NUMBER 15- D-13549  
NW NW NW, SEC. 11, T. 20 S, R. 11 W/E  
\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name West Silica Well # 5  
County Barton 123.50  
Well Total Depth 3800 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 219'/200 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ x \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Quinoco Petroleum Inc. License Number 3613

Address Box 37811, Denver, Colorado

Company to plug at: Hour: \_\_\_\_\_ PM Day: 30 Month: Nov Year: 19 88

Plugging proposal received from Peter Minsche

(company name) Quinoco Petroleum Inc. (phone) \_\_\_\_\_

were: Cement with 50 sks Common, 200 sks of 60/4- Pozmix 500# of Hulls.

Cement history 219' of 10 3/4" cemented w/200 sks

3281' of 6" cemented w/100 sks to surface

3800' of 4" cemented w/250 sks to surface

Well plated, pumped down 4".

Plugging Proposal Received by \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1988  
12-29-88  
CONSERVATION DIVISION  
Wichita, Kansas  
Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15 Day: 30 Month: Nov Year: 19 88

ACTUAL PLUGGING REPORT Nov 29, 1988, ran 50 sks of Common 100 sks of 60/40

Pozmix 3% Cal Cl 6% Gel, 100 sks of 60/40 Pozmix 3% Ca Cl 6% Gel w/500# of Hulls. Went on

vacuum. Ran wireline to 750'. Nov 30, 1988 ran wireline to 714'. Pumped water and filled

hole, blew plates at 150#. Rewelded, pressured up to 500#. Ran 69' of 1 in. O.D. tubing.

Pumped in 40 sks of 60/40 Poz. Plugged at 4:15 P.M. Cemented by Halliburton.

Remarks: \_\_\_\_\_

(If additional description is necessary, use BACK of this form.)

I (did xxxxxxxx) observe this plugging.

Signed Bruce D. Basye

(TECHNICIAN)  
Bruce D. Basye

INVOICED  
DATE 1-6-89

INV. NO. 23517