

4 060172

3-8

156 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-22,420-0000

E2 NE SW, SEC. 12ⁿ, T 16 S, R 13 W/E

1980 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Phillips A Well # 1

Operator: State of Kansas Fee Fund

County Barton

Name & Address _____

Well Total Depth 3391 feet

Robert D. Reed abandoned well

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well xxxxxxx Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor State of Kansas License Number _____

Address District #4 Hays, KS

Company to plug at: Hour: 8:30AM Day: 8 Month: March Year: 19 91

Plugging proposal received from District #4 staff.

(company name) _____ (phone) _____

were: Order 350 sxs. 60/40 pos 8% gel and hulls.

RECEIVED
STATE CORPORATION COMMISSION

Run tubing to TD and circ. cement to surface.

3-22-91 MAR 22 1991

Well had perfs sanded back and cement spotted on top of sand.

CONSERVATION DIVISION
WICHITA, KANSAS

Casing had been shot off and pulled at 640'.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All XXXXXXXXXX Part _____ None _____

Operations Completed: Hour: 8:30PM Day: 8 Month: March Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" to 266', 4 1/2" to 3382'. Washed hole down to 640' with tubing and mud pump. Stung into casing and ran tubing to 3058'. Pmp 100 sxs. cement. Pull tbg.

to 855' and perf anhydrite at 890' and run tbg to 920'. Pmp 25sxs. cement and pull tbg to 600'. pmp 225 sxs. cement. Did not circ. Tied onto tbg. But hole collapsed and stuck tubing.

Backed off tubing leaving 15 jts of tubing in hole. Ordered additional cement and pmp 50 sxs. cement after pulling casing. Max 700# SIP 700#

Remarks: Halliburton Cementing, DS&W well Service, Wire-Tech perforators, Parsons Tank Serv.
(If additional description is necessary, use BACK of this form.)

I (did XXXXXXXXXX) observe this plugging.

Herb S.

Signed *[Signature]*
(TECHNICIAN)

Herb Deines