

4-20-88

6 070670

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-22,721 00-01
SW NW SE SEC. 12, T 16 S, R 13 W
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5286

Lease Name Cain Well # 1

Operator: Amer Kan Resources Group LTD
Name & Address: 422 Union Center/150 N Main
Wichita, Ks. 67202

County Barton 116.68

Well Total Depth 3,590 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: 1:00 PM Day: 20 Month: April Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pulling (phone) 316-793-9721

were: 8 5/8"-308' SP cir w/ 175 sx cmt, 5 1/2" casing set @ 3590' w/ 150 sx cmt. Perfs 3378-3052'
at bottom sand 50' above perforations to 3000' and w/ 5 sx cmt. Shot casing once, recovered
2403'. Proposa 125 sx 65/35 pozmix, 10% gel, 2% additive and 5 sx hulls, load and pressure
8 5/8" with cement, Shut in under pressure.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45PM Day: 20 Month: April Year: 19 88

ACTUAL PLUGGING REPORT Ordered 125 sx 65/35 pozmix, 10% gel, 2% additive, and 5 sx hulls.

Pumped in with pump truck. Pumped in 8 5/8", 25 sx cmt. followed with another 100 sx
cmt with 5 sx hulls added in. Maximum pressure 500 psi and 200 psi shut in.

Cemented by Allied Cementing Co. STATE CORPORATION COMMISSION

7-6-88 1111 6 1022

Remarks: (If additional description is necessary, use BACK of this form.)
CONSERVATION DIVISION
Wichita, Kansas

I () observe this plugging.

Signed Marion J. Schmidt (TECHNICIAN)

DATE 7-7-88

REV. NO. 21192