

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.009.14460.0000

LEASE NAME Stueckemann

WELL NUMBER A-5

990' Ft. from S Section Line

330' Ft. from E Section Line

SEC. 11 TWP. 20S RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed 9-17-38

Plugging Commenced 7-31-91

Plugging Completed 8-29-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hallwood Petroleum, Inc.

ADDRESS P.O. Box 378111, Denver, CO 80237

PHONE#(303) 850-7373 OPERATORS LICENSE NO. 3613

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? 12-30-91

Producing Formation Arbuckle Depth to Top _____ Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

RECEIVED

KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surf.	To	Size	Put in	Pulled
<u>Arbuckle</u>		<u>Surf.</u>	<u>220</u>	<u>10 3/4"</u>	<u>220'</u>	<u>DEC 30 1991</u>
		<u>Surf.</u>	<u>3271</u>	<u>7"</u>	<u>3271'</u>	

CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 10 3/4" set at 220' w/200 sks. & 7" set at 3271' w/100 sks. Top perf at 3271'. Rn 2 7/8" tubing to 850' and spotted cement to surface. 187 sks 60/40 poz total. Pulled tubing and hooked on to 7" casing. cement w/263 sks w/500 psi. Pumped in 10 3/4" 0 sk w/1100 psi. Checked cmt. Fill up in 7' was 265' from surf. plug back to surf w/ready mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287

Address P.O. Box 579, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc.

STATE OF Colorado COUNTY OF Denver, ss

Andrew L. Marciano (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Donna R. Saurne

(Address) Aurora CO

SUBSCRIBED AND SWORN TO before me this 10 day of Oct, 19 91

DONNA R SAURNE
Notary Public

My Commission Expires: 8-25-92