


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 11 Twp. 20S Rge. 11 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ NE $\frac{1}{4}$ NW $\frac{1}{4}$
Lease Owner Stanolind Oil and Gas Company
Lease Name F. Panning "A" Well No. 7
Office Address Box 1654, Oklahoma City, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12-2- 1937
Application for plugging filed 8-15- 1951
Application for plugging approved 8-17- 1951
Plugging commenced 8-30- 1951
Plugging completed 9-6- 1951
Reason for abandonment of well or producing formation depleted
If a producing well is abandoned, date of last production 3-31- 1951
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. D. Stough
Producing formation Arbuckle Depth to top 3275 Bottom 3287 Total Depth of Well 3287 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------------------|------------|-------------|-------------|------------|-------------|-------------|
| <u>Arbuckle or</u> | <u>Oil</u> | <u>3275</u> | <u>3287</u> | <u>13"</u> | <u>195</u> | <u>None</u> |
| <u>Siliceous Lime</u> | | | | <u>6"</u> | <u>3296</u> | <u>2266</u> |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

C/Rock 3287' - 3270'
6 sx cement 3270' - 3234'
Hvy. mud 3234' - 209'
C/Rock 209' - 199'
20 sx cement 199' - 169'
Hvy. mud 169' - 15'
10 sx cement 15' to bottom of cellar

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to G. A. Younie
Address Box 7, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

G. A. Younie (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____

Box 7, Ellinwood, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of September 1951

My commission expires May 2, 1955

23-5091-s

8-50-10M

SEP 8 X 1951 9-8-51

Notary Public.

PLUGGING
FILE SEC 11 T 20 R 16
BOOK PAGE 104 UNH 6

| | | |
|-----------------------|------|------|
| Surface sand and clay | 0 | 95 |
| Shale and shells | 96 | 198 |
| Red bed | 198 | 495 |
| Anhydrite | 495 | 523 |
| Shale and shells | 523 | 1080 |
| Salt | 1080 | 1100 |
| Shale and shells | 1100 | 1374 |
| Broken lime | 1374 | 1782 |
| Lime | 1782 | 1840 |
| Broken lime | 1840 | 2182 |
| Lime and shale | 2182 | 2268 |
| Broken lime | 2268 | 2566 |
| Lime | 2566 | 2955 |
| Broken lime | 2955 | 3024 |
| Lime | 3024 | 3260 |

Top Siliceous 3275
Cable tool cores

| | | |
|-----------------------------|------|------|
| Lime - no increase | 3279 | 3282 |
| Lime - little saturation | 3282 | 3285 |
| Lime - good sat. & porosity | 3285 | 3286 |
| Lime - hard gray lime | 3286 | 3287 |

TOTAL DEPTH 3287

Acidizing Record
acidized with 2000 gallons
Dowell xx, treatment in 1
hour 18 minutes

| | |
|--------------------------|----------|
| Date of first work | 10-4-37 |
| Date drlg. commenced | 10-23-37 |
| Date drlg. completed | 11-30-37 |
| Date well completed | 12-2-37 |
| Date potential effective | 12-3-37 |

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 X 1951
PLUGGING
FILE SEC 11 110 R 11
PAGE 104

640 Acres
N R 11 W

STANOLIND OIL AND GAS COMPANY WELL RECORD

| | | | | | |
|--|-----|----|---|--|-----|
| | | #7 | ○ | | |
| | 160 | | | | 160 |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | 160 | | | | 160 |
| | | | | | |
| | | | | | |

Locate Well Correctly

COUNTY Barton, SEC. 11, TWP. 20 s, RGE. 11 w
COMPANY OPERATING Stanolind Oil and Gas Company
OFFICE ADDRESS P.O. Box 591 - Tulsa, Oklahoma
FARM NAME Fred Panning "A" WELL NO. 7
DRILLING STARTED 10-23- 37 DRILLING FINISHED 11-30- 37
WELL LOCATED SE NE NW 1650 ft. North of South
2310 Line and _____ ft. East of West Line of Quarter Section.
ELEVATION (Relative to sea level) DERRICK FLR. 1761 GROUND 1758
CHARACTER OF WELL (Oil, gas or dry hole) oil

OIL OR GAS SANDS OR ZONES

| Name | | From | To | Name | | From | To |
|------|----------------|------|------|------|--|------|----|
| 1 | Siliceous Lime | 3275 | 3287 | 4 | | | |
| 2 | | | | 5 | | | |
| 3 | | | | 6 | | | |

WATER SANDS

CASING RECORD

[illegible]

Liner Record: Amount

Kind

Top

Bottom

CEMENTING AND MUDDING RECORD

[illegible]

NOTE: What method was used to protect sands when outer strings were pulled?

NOTE Were bottom hole plugs used? _____ If so, state kind, depth set and results obtained

TOOLS USED

| | | | | | | |
|-----------------------------|-----------|---------|------|----------------|--|---------|
| Rotary tools were used from | 0 | feet to | 3279 | feet, and from | | feet to |
| Cable tools were used from | 3279 | feet to | 3287 | feet, and from | | feet to |
| Type Rig | 94' Steel | | | | | |

PRODUCTION DATA

Swabbed 15 bbls. per hour before acidizing through 6" casing.

| | | | | |
|--|---------------|----------|------------------|-----------|
| Production first 24 hours | bbls. Gravity | Emulsion | per cent., Water | per cent. |
| 8 hr. state test 1654 bbls. no water, pumping 37-54 SPM thru 3" tubing & 6" casing. | | | | |
| Production second 24 hours | bbls. Gravity | Emulsion | per cent., Water | per cent. |

If gas well, cubic feet per 24 hours _____ Rock Pressure, lbs. per square inch _____

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct and complete according to the records of this office and to the best of my knowledge and belief.

Subscribed and sworn to before me this the 18th day of December, 1937

My commission expires May 3, 1941

Notary Public.

Nº 045464

STANOLIND OIL AND GAS COMPANY

FIELD PURCHASE ORDER

DATE Aug 18, 1951

ORDERED FROM Kansas State Corporation

ADDRESS 800 Bethune Boulevard Columbia, Kc

RENDER INVOICE IN DUPLICATE FOR EACH ORDER. SHOW ORDER NUMBER ON ALL COPIES OF INVOICE AND MAIL TO

STANOLIND OIL AND GAS COMPANY Call 11/11/1962 Room

CITY

STATE

DELIVER MATERIAL TO _____

[illegible]

CHARGE TO E. Tamm Co. 1001-7 (P.C.A.)

USED FOR Plugging leak

☐ ORIG. CONST. ☐ OPERATIONS
☐ REPLACEMENT ☐ REPAIRS

TERMS

BY ACCEPTANCE OF THIS ORDER SELLER AGREES TO
AND SHALL BE BOUND BY THE TERMS AND CONDITIONS
PRINTED ON THE BACK HEREOF.

STANOLIND OIL AND GAS COMPANY

B

No. 1 This Order is given on the express condition and agreement that the Seller, its heirs, successors, assigns and legal representatives, shall forever protect, indemnify and save harmless the Buyer against any and all claims, suits in law or equity, judgments, court costs, attorneys' fees, and other liabilities, demands or losses in any manner arising out of alleged infringement of any patent, copyright and trade mark rights because of the possession, use or sale by the Buyer or its agents of the subject matter to which this agreement relates, it being understood that said Buyer will promptly notify said Seller of the bringing of said suits, and that Seller shall have the right to be represented in the defense thereof by counsel of its own selection and at its own expense; it is further of the essence of this agreement and a part of the consideration for entering into it by the Buyer that the Buyer shall have a free and unrestricted right and license to use said subject matter in any and all arts and under all patents in or under which Seller may now or hereafter have an interest.

No. 2 In the event Buyer and Seller have heretofore entered into a written agreement providing for the purchase and sale of the products mentioned in this order and the period covered by such prior agreement has not expired, then this order shall be considered as made by Buyer and accepted by Seller on the same terms and conditions set forth in said prior agreement and nothing herein contained shall be held in any manner to be a modification of such prior agreement of purchase.

No. 3 Seller represents that the sale of the article or articles referred to herein, and the price therefor and delivery thereof will conform to all applicable federal and state laws, orders, rules and regulations.