

State of Kansas



15.009.04847.0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. B. E. Ash of Bea Drilling Company has this

date requested permission to plug the following described well:

Mr. Bea Drilling Company guarantees payment of the plugging fee.

Operator's full Name: Bea Drilling Company

Complete Address: P. O. Box 247, Ellinwood, Kansas 67526

Lease Name: Brenn "A" Well No. # 3

Location: NE NW SE Sec. 15 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3332 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Ralph Glenn was instructed to plug the well as follows:

8 5/8" csg. 226' Cwc. Perf. 3000'

Sanded hole back to 2980' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 2 sax hulls, 20 sax mud, 1 sax

hulls, & displaced 100 sax cement with Allied Cementing Company's

pump truck, cementing from 340' to base of cellar.

Very truly yours,

Don L. Brown  
Conservation Division Agent