



15.009.30179.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
AIVIN F. GRAUERHOLZ Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1965
4-15-65
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. R. T. Overly of Bea Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Bea Ash guarantees payment of the plugging fee.

Operator's full Name: Bea Drilling Company, Inc.

Complete Address: Box 247, Ellinwood, Kansas

Lease Name: Ringering Well No. # 3

Location: W/2 NW NE Sec. 15 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3338 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Ralph Glenn was instructed to plug the well as follows:

8 5/8" 222' Cwc.

Sanded hole back to 3290' & dumped 5 sax cement with
dump bailer. Pulled pipe. Mudded hole to 220'; set rock
bridge; displaced 4 sax cement with dump bailer. Let set
over-nite; Bailed hole dry; displaced 25 sax cement. Mud to
40'; set rock bridge; displaced 10 sax cement, cementing
to base of cellar.

Don Truman
Conservation Division Agent