



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dick Mead of Sterling Drilling Company has this
date requested permission to plug the following described well:Mr. Kansas Petroleum, Inc. guarantees payment of the plugging fee.Operator's full Name: Kansas Petroleum, Inc.Complete Address: 1620 Vickers K S B & T Bldg., Wichita, KansasLease Name: Kowalsky Well No. # 1Location: APP NE NW NE
330' SNL 1220 WEL NE Sec. 11 Twp. 20 Rge. 11(E)(W) WCounty: Barton Total Depth 3330 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Dick Mead was instructed to plug the well as follows:8 5/8" csg. 215' Cwc.Circulated hole with heavy mud to 480', set plug, & displaced 40 saxcement thru drill pipe. Mud to 200' & displaced 25 sax cement thrudrill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 saxcement with Sun Cementing Company's pump truck, cementing to base ofcellar.

Very truly yours,

Conservation Division Agent