

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-21262-00-00
Spot: NWNWSENW Sec/Twnshp/Rge: 10-26S-8E
1450 feet from N Section Line, 1580 feet from W Section Line
Lease Name: RICE Well #: 6
County: GREENWOOD Total Vertical Depth: 2545 feet

Operator License No.: 5697
Op Name: JACKSON BROTHERS, L.L.C.
Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2372		
PROD	4.5	2526		200 SX
SURF	8.625	40		30 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/17/2018 12:00 AM
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC
Proposal Revd. from: ROSCOE G. JACKSON II Company: _____ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 1780-1730 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1200-1150 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed: 05/17/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1780', pumped 20 sxs cement, pulled tubing to 1200' pumped 10 sxs cement, pulled tubing to 150', pumped 75 sxs cement to surface, gel spacers between cement plugs,

Perfs:

Top	Bot	Thru	Comments
2487	2497		
2372	2439		
1800	1807		

RECEIVED
KCC DIST # 3
JUN 18 2018
CHANUTE, KS

INVOICED
JUL 20 2018

MH

Remarks:
Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3907
 Foreman Rick Ledford
 Camp Eureka 163

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
5-17-18	1008	RICE # 6	10	26S	8E	GW	Ks
Customer Jackson Brothers LLC			Unit #	Driver	Unit #	Driver	
Mailing Address 114 E. 3rd			104	Alan M.			
City Eureka			112	Allen B.			
State Ks			145	Rick L.			
Zip Code 67045			121	Craig M.			

Job Type P.T.A old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
 Casing Depth _____ Hole Size _____ Slurry Wt. 14# Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 7.0 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meetings Rig up to 2 3/8" tubing. Plugging orders as follows:
20 sks @ 1780'
10 sks @ 1200'
75 sks @ 150' to surface (inside + outside of 4 1/2")
105 sks total
gel-spacer between plugs
"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	10	Mileage	3.95	39.50
C203	105 sks	60/40 Perm. cement	12.75	1338.75
C206	360 #	4% gel	.20	72.00
C286	200 #	gel-spacer	.20	40.00
C108A	4.5 ²	tax mileage bulk trk	m/c	345.00
C113	2 1/2 hrs	80 Btl vac. TRK	85.00	212.50
C224	3000 gals	city water	10.00/1000	30.00
INVOICED				
JUL 20 2018				
			Subtotal	2827.75
			- 5% disc.	<152.00>
			Sales Tax	212.08

Authorization _____ Title _____ Total 2887.83

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.