

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19216-00-00
Spot: S2SEW Sec/Twnshp/Rge: 3-28S-6E
2310 feet from N Section Line, 1980 feet from W Section Line
Lease Name: KRAMER Well #: 10
County: BUTLER Total Vertical Depth: 3065 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5	3059		125 SX
SURF	8.625	223		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICH CLARK/JOHN HILL/H Company: _____ Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/01/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING, CIRCUALTING VARIOUS BRIDGES FROM 65'-3,000'. RIH WITH TUBING @ 3000', QWS MIXED AND PUMPED 30 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS & DISPLACED IN CASING. LAYED DOWN TUBING. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (4 HOLES). RIH WITH TUBING @ 260', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 55 SXS 60/40 POZMIX TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO 5 1/2" CASING. QWS MIXED & PUMPED 70 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED BETWEEN ALL 3 STRINGS.

Perfs:

Top	Bot	Thru	Comments
3059	3065	OH	

INVOICED
JUL 20 2018

Remarks: DENIED TA / COMPLIANCE AGREEMENT

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

✓