

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23671-00-00
Spot: NENWNE Sec/Twnshp/Rge: 10-28S-6E
4950 feet from S Section Line, 1687 feet from E Section Line
Lease Name: GILLILAND B Well #: 1X
County: BUTLER Total Vertical Depth: 2350 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2250		
PROD	4.5	2349		135 SX
SURF	8.625	202		135 SX
T1	2.375	2310		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: _____ Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/08/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

TUBING & PACKER HUNG UP IN HOLE, PRESSURE ON TUBING, SWEDGED INTO TUBING. QWS ESTABLISHED A PUMPING RATE, AND MIXED & PUMPED 35 SXS 60/40 POZMIX 3% CC & 100# HULLS & DISPLACED IN CASING. S.I. # 1200# SDON. 5-3-08, SHOT TUBING OFF @ 1850', LAYED DOWN TUBING. RIH ON WIRELINE, PERFERATED SQUEEZE HOLES 250'-251' (4 HOLES). SDON. 5-8-2019 RIH W/TUBING AT 260', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 65 SXS TO SURFACE, LAYED TUBING DOWN, SWEDGED INTO 4.5" CASING, MIXED AND PUMPED 55 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. TOPPED WELL BACK TO SURFACE WITH 10 SXS.

Perfs:

Top	Bot	Thru	Comments
2266	2272	CSG	
2104	2111	CSG	

INVOICED
JUL 20 2018

Remarks: DENIED TA/ COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1/8