

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19331-00-00
Spot: NESWNW Sec/Twnshp/Rge: 10-27S-6E
3820 feet from S Section Line, 3995 feet from E Section Line
Lease Name: MARSHALL Well #: 1A
County: BUTLER Total Vertical Depth: 3124 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3122		80 SX
SURF	8.625	200		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/08/2018 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICH CLARK/HAYS WILSO Company: _____ Phone: (405) 526-0111

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/08/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH WITH TUBING @ 3120', QWS ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL 3% CC AND 100# HULLS & DISPLACED IN CASING. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES (250'-251'-) 4 HOLES. RIH WITH TUBING @ 260', QWS ESTABLISHED CIRCULATION, MIXED AND PUMPED 65 SXS 60/40 POZMIX 4% GEL 2% CC & 100# HULLS TO SURFACE. LAYED DOWN TUBING SWEDGED INTO 5.5" CASING & PUMPED 80 SXS 60/40 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED.

Top	Bot	Thru	Comments
3120	3124	OH	

INVOICED
MAY 20 2018

Remarks: DENIED TA / COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1/3K