

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-23675-00-01
Spot: NENESW Sec/Twnshp/Rge: 30-27S-8E
2310 feet from S Section Line, 7258 feet from E Section Line
Lease Name: LUCAS Well #: 1
County: BUTLER Total Vertical Depth: 3270 feet

Operator License No.: 33556
Op Name: DRAKE EXPLORATION, LLC
Address: 15894 294TH CIR #19
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	4.5	2740		
CIBP	4.5	3160		
PROD	4.5	3213		150 SX
SURF	8.625	201		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/01/2018 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DARREN BROYLES Company: _____ Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2740 WITH 2 SXS. PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 05/01/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2740', DUMP BAILED 2 SXS CEMENT ON TOP OF PLUG. LOADED HOLE, PRESSURED CASING, HELD OK. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 250'-251' (2 HOLES). SWEDGED INTO 4 1/2" CASING, ELITE CEMENTING ESTABLISHED CIRCULATION, MIXED AND PUMPED 80 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #3880.

Perfs:

Top	Bot	Thru	Comments
3204	3208		CSG
2776	2780		CSG

INVOICED
JUL 20 2018

Remarks: DENIED TA/ LACK OF LEASE

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

1/4