

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-21586-00-00  
Spot: S2SENWNW Sec/Twnshp/Rge: 13-21S-14W  
4267 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: WRIGHT Well #: 3  
County: STAFFORD Total Vertical Depth: 3692 feet

Operator License No.: 6170  
Op Name: GLOBE OPERATING, INC.  
Address: PO BOX 12  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		860		
CIBP		3650		
PROD	5.5	3690	0	WITH 150 SX CMT
SURF	8.625	292		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/03/2018 10:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING Phone: (620) 792-7607

Proposed Plugging Method: RUN TBG TO 3400' & SPOT 30 SX CMT WITH 150# HULLS. TOOH WITH TBG. SET CIBP @ 850'. PERFORATE AT 840'. RUN TBG TO 840' & SPOT 50 SX CMT WITH 25# HULLS IN LAST 20 SX CMT. TOOH WITH TBG. PERFORATE AT 320'. ATTEMPT TO BREAK CIRCULATION WITH WATER. IF SUCCESSFUL CIRCULATE CMT TO SURFACE LEAVING THE CASING & ANNULUS FULL OF CMT. OF WELL WILL NOT CIRCULATE LOAD THE 5 1/2" CASING WITH HULLS & CMT. PUMP CMT & HULLS DOWN THE ANNULUS (AT LEAST 50 SX CMT) STAGE UNTIL ANNULUS WILL STAY FULL OF CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 05/04/2018 10:00 AM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SQUEEZED PERFS AT 3440'-3446'. OPEN KC PERFS AT 3476'-3482'. CASING LEAKS AT 1400' +/- & ABOVE 850'. TIH WITH TBG TO 3400' & PUMP 30 SX CMT WITH 150# HULLS. TOOH WITH TBG. SET CIBP @ 860'. RATTY CASING AT 850'. PERFORATE AT 840'. TIH WITH CASING TO 840'. PUMP 370 SX CMT. GOOD CIRCULATION OF WATER BACK ON BOTH SIDES. RAN OUT OF CMT. TOOH WITH TBG. SDON. 5/4/18: TIH WITH TBG & TAG CMT AT 330'. BREAK CIRCULATION WITH WATER. NO BACKSIDE CIRCULATION. PUMP 50 SX COMMON CMT WITH 3% CC TO FILL 5 1/2" CASING. POOH WITH TBG. TIE ONTO BACKSIDE & PUMP 150 SX COMMON CMT 3% CC WITH 150# HULLS TO FILL TO SURFACE. CMT HOLDING STEADY AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3476	3482		
3440	3446		

**INVOICED**  
**JUL 20 2018**

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CEMENT WITH 3% CC BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed Ken Scofield  
(TECHNICIAN)

RECEIVED  
MAY 10 2018  
KCC DODGE CITY