

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-20312-00-00  
Spot: SENESWNW Sec/Twnshp/Rge: 10-26S-8E  
1940 feet from N Section Line, 1150 feet from W Section Line  
Lease Name: RICE Well #: 2  
County: GREENWOOD Total Vertical Depth: 2550 feet

Operator License No.: 5697  
Op Name: JACKSON BROTHERS, L.L.C.  
Address: 116 E 3RD ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2541		110 SX
SURF	8.625	45		30 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2018 12:00 AM  
Plug Co. License No.: 6112 Plug Co. Name: LONG DRILLING COMPANY, LLC  
Proposal Revd. from: ROSCOE G. JACKSON II Company: \_\_\_\_\_ Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 2470-2420 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1260-1210 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/27/2018 12:00 AM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

used dump baler spotted 7 sxs cement @ 2470', set bridge plug @ 1260' pumped 10 sxs cement, built bridge @ 150' pumped 35 sxs cement to surface

Perfs:

Top	Bot	Thru	Comments
2498	2517		

RECEIVED  
KCC DIST # 3  
MAY 15 2018  
CHANUTE, KS

MH

INVOICED  
JUL 20 2018

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)