

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-20320-00-00
Spot: SENESENW Sec/Twnshp/Rge: 31-26S-8E
3620 feet from S Section Line, 2950 feet from E Section Line
Lease Name: DRUMM INSTITUTE Well #: 7
County: BUTLER Total Vertical Depth: 2795 feet

Operator License No.: 35164
Op Name: JIM SNYDER, INC.
Address: PO BOX 109
HAMILTON, KS 66853

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2793		80 SX
SURF	8.625	149		85 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2018 8:00 AM
Plug Co. License No.: 35164 Plug Co. Name: JIM SNYDER, INC.
Proposal Rcvd. from: JOEL SNYDER Company: _____ Phone: (620) 344-6042

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 05/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH WITH TUBING @ 2582', SNYDER MIXED & PUMPED .5 SX GEL WITH 5 BBLS WATER, (GEL PLUG) AND 7 SXS CLASS A CEMENT & DISPLACED IN CASING. TAGGED PLUG @ 2379'. RIH ON WIRELINE, CUT CASING @ 259', LAYED DOWN 8 JOINTS 5 1/2" CASING (259'). BAILED WELL @ 259', CMC POURED 4.25 YARDS OF SLURRY FROM 259'-0'. CEMENT AT SURFACE. CEMENT TICKET #401580 AND 401582.

INVOICED
JUL 20 2018

Perfs:

Top	Bot	Thru	Comments
2679	2698		

Remarks: DENIED TA/ COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)

Handwritten mark