

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19392-00-00
Spot: SESWNE Sec/Twnshp/Rge: 28-34S-12E
3160 feet from S Section Line, 1911 feet from E Section Line
Lease Name: BROOKS Well #: 15
County: CHAUTAUQUA Total Vertical Depth: 1060 feet

Operator License No.: 35368
Op Name: JONES OIL EXPLORATION, LLC
Address: PO BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 7		1050		0 SX
PROD 7		1056		
SURF 14		20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/10/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MATT JONES Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: Cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 04/11/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Washed and drilled 1" to 1056' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 600' and 275'. Ran 1" back into 600' and spotted 30 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 162 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
995	1010		

RECEIVED
KCC DIST # 3
MAY 15 2018
CHANUTE, KS
DS

INVOICED
JUL 20 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT WITH OPERATOR AND KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)