

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22268-00-00  
Spot: NWSWNENW Sec/Twnshp/Rge: 9-29S-15W  
694 feet from N Section Line, 1461 feet from W Section Line  
Lease Name: SMITH A Well #: 1  
County: PRATT Total Vertical Depth: 4920 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 100 S MAIN ST, STE 420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4350		WITH 2 SX CMT
CIBP		4490		
CIBP		4700		
PROD	5.5	4803	2013	WITH 200 SX CMT
SURF	10.75	292		WITH 375 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2018 8:55 AM  
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC  
Proposal Rcvd. from: ROBIN BROWN Company: ROBIN BROWN CONSULTING Phone: (620) 546-4801

Proposed Plugging Method: CIBP @ 4480' WITH 2 SX CMT. CIBP @ 4350' WITH 2 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 330' WITH 75 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2018 10:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 4490'. CIBP @ 4350' WITH 2 SX CMT. 1ST PLUG AT 893' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 318' WITH 75 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT TO SURFACE. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
4705	4710		
4700			
4523	4554		
4384	4692		

INVOICED  
JUL 20 2018

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
MAY - 7 2018  
KCC DODGE CITY

*MP*

*FA*