

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-20526-00-00  
Spot: S2S2NW Sec/Twnshp/Rge: 13-24S-15W  
3058 feet from S Section Line, 3911 feet from E Section Line  
Lease Name: ENGLISH-REID Well #: 2  
County: STAFFORD Total Vertical Depth: 4332 feet

Operator License No.: 5474  
Op Name: NORTHERN LIGHTS OIL COMPANY, LL  
Address: PO BOX 164  
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4080		WITH 2 SX CMT
CIBP		4290		
PROD	5.5	4332	0	WITH 125 SX CMT
SURF	8.625	295		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2018 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: PRESTON DREILING Company: NORTHERN LIGHTS OIL CO. Phone: (785) 639-2099

Proposed Plugging Method: PICK UP TBG & SET BOTTOM PLUG AT 4075' WITH 50 SX CMT & 100# HULLS. PERFORATE AT 1000' & 340'. PLUG THROUGH TBG AT 1000' WITH 50 SX CMT FOLLOWED BY 50 SX CMT WITH 50# HULLS. PULL TBG TO 340' & PUMP CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/24/2018 8:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 4080' WITH 2 SX CMT ON TOP. PRESSURE TEST CASING TO 200 PSI FOR 5 MINUTES. PERFORATE AT 1000' & BREAK CIRCULATION WITH WATER. PUMP 300 SX CMT TO SURFACE. HOLE FULL INSIDE & PUT OF 5 1/2" CASING. 4/27/18: USED 30 SX CMT TO TOP OFF 5 1/2" CASING.

INVOICED  
JUL 20 2018

Perfs:

Top	Bot	Thru	Comments
4266	4277		
4259	4260		
4116	4118		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD SERVICES.  
Plugged through: CSG

District: 01

Signed Ken Scofield  
(TECHNICIAN)

RECEIVED  
MAY - 7 2018  
KCC DODGE CITY