

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23799-00-02
Spot: SENWSWSW Sec/Twnshp/Rge: 30-19S-21W
959 feet from S Section Line, 331 feet from W Section Line
Lease Name: MOORE HEIRS C Well #: 1
County: NESS Total Vertical Depth: 4437 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1550		
PC		1508		WITH 250 SX CMT
PROD	5.5	4416	0	WITH 75 SX CMT
SURF	8.625	309		WITH 180 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/30/2018 8:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: SCOTT BOEH Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: RUN TBG TO 4380' WITH 50 SX CMT & 150# HULLS. CIBP @ 1550'. TBG TO 1550' & CIRCULATE TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/30/2018 2:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4383' & MIXED 50 SX CMT & 150# HULLS. PULLED TBG & RAN CIBP TO 1550'. RAN TBG TO 1538' & MIXED 150 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & MIXED 25 SX CMT. PRESSURED TO 300# & HELD.

INVOICED
JUL 20 2018

Perfs:

Top	Bot	Thru	Comments
4424	4437		
4422	4424		
4417	4420		
4416	4437		
4327	4330		

Remarks: **COMPLAINCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
MAY - 7 2018
KCC DODGE CITY