

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21983-01-00  
Spot: NENWNENE Sec/Twnshp/Rge: 17-34S-6W  
250 feet from N Section Line, 980 feet from E Section Line  
Lease Name: DANIELLE 3406 Well #: 1-17H  
County: HARPER Total Vertical Depth: 5785 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 SX
L1	4.5	9482		
PROD	7	5785	1306	390 SX
SURF	9.625	670		335 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2018 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6165

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/24/2018 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4550'. CIRCULATE HOLE WITH 170 BBLs MUD AND 50 SX CEMENT. CUT AND LAY DOWN 1306' OF 7" CASING. TIH WITH TUBING TO 1100' AND SPOT 50 SKS CEMENT. PULL TUBING TO 720' AND SPOT 50 SXS CEMENT. PULL TUBING TO 300' & CIRCULATED CEMENT TO SURFACE WITH 95 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
5342	9048		

INVOICED  
JUL 20 2018

Remarks: ORR ENTERPRISES. CLASS "C" CEMENT. TMD = 9485

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)