

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-27609-00-00
Spot: NWNE Sec/Twnshp/Rge: 18-33S-10E
5033 feet from S Section Line, 881 feet from E Section Line
Lease Name: WELLS Well #: 3
County: CHAUTAUQUA Total Vertical Depth: 1650 feet

Operator License No.: 35116
Op Name: SM OIL & GAS, INC.
Address: PO BOX 189
SKIATOOK, OK 74070

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
SURF	8.625	42		10 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/12/2018 12:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: JOEL POTTS Company: _____ Phone: (918) 977-1178

Proposed Plugging Method: Plug in accordance with KCC rules and regulations. Gel hole, place 100 cement plug at TD, place 50' cement plug at 1000', place cement from 550' to surface, restore location. DRY HOLE

Plugging Proposal Received By: DUANE SIMS Witness Type: NONE
Date/Time Plugging Completed: 04/19/2018 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 2" to 1635' gelled hole and spotted 20 sack plug. Pulled up to 1009' and spotted 10 sack plug. Pulled up to 551' and circulated cement to surface. Pulled 2" and topped well off. A total of 175 sacks of 60/40 pozmix with 4% gel was used to plug this well.

RECEIVED
KCC DIST # 3
MAY 15 2018
CHANUTE, KS

DS

INVOICED
JUL 20 2018

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)