

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-19025-00-00
Spot: NWNWNWNW Sec/Twnshp/Rgc: 34-18S-2E
4962 feet from S Section Line, 4980 feet from E Section Line
Lease Name: SCULLY A Well #: 2-34
County: MARION Total Vertical Depth: 2912 feet

Operator License No.: 5399
Op Name: TREK AEC, LLC
Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2911		0 SX
SURF	8.625	0		0 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/27/2018 2:00 PM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Revd. from: TANNER NELSON Company: _____ Phone: (620) 755-2571

Proposed Plugging Method: AS PER KCC RULES & REGS. USUALLY THIS CONSISTS OF A CIBP OR 50' SAND PLUG AT BOTTOM COVERED WITH A 5 SACK CEMENT PLUG. FILL FROM 250' TO SURFACE WITH CEMENT (ANNULUS AND CASING). CUT CASING OFF BELOW GROUND LEVEL. RESTORE GROUND AS NEEDED.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2018 2:00 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

4/26/18 PULLED TUBING STRINGS (1 1/2" INSIDE OF 2 7/8"), SANDED OFF BOTTOM WITH 55' OF SAND. RAN BAILER IN AND TAGGED @ 2857' TOPPED WITH 5 SX OF COMMON CEMENT. RAN 1" DOWN BACKSIDE TO 185' TAGGED CEMENT REMOVED 1 JOINT TO 175'. PERFORATED AT 250'. THEN RAN 9 JOINTS 2 7/8" TUBING TO 250'. 4/27/18 QES HOOKED UP TO 2 7/8" AND PUMPED 75 SX AND CIRCULATED TO SURFACE. THEN HOOKED UP TO 1" AND PUMPED 25 SX AND CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2857	2912	CSG	
0	250	CSG	

INVOICED
JUL 20 2018

Remarks: QES TICKET #55340

Plugged through: CSG

District: 02

Signed  (TECHNICIAN)