

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21078-00-00  
Spot: NWNENWNE Sec/Twnshp/Rge: 26-29S-19W  
5020 feet from S Section Line, 1664 feet from E Section Line  
Lease Name: UNRUH B Well #: 1  
County: KIOWA Total Vertical Depth: 5172 feet

Operator License No.: 5004  
Op Name: VINCENT OIL CORPORATION  
Address: 200 W DOUGLAS AVE #725  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5050		WITH 2 SX CMT
PROD	4.5	5171	0	WITH 75 SX CMT
SURF	8.625	521		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/30/2018 12:00 PM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Rcvd. from: SPENCER SIROKY Company: FOSSIL DRILLING, INC. Phone: (620) 770-0636

Proposed Plugging Method: CIBP @ 5050' WITH 2 SX CMT. PLUG AT 1320' WITH 15 SX GEL & 50 SX CMT. PLUG AT 560' WITH 50 SX CMT. PLUG AT 240' WITH 30 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/30/2018 4:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5050' WITH 2 SX CMT. COULD GET ONLY 900' OF STRETCH. PERFORATED AT 1320' & ESTABLISHED A PUMP RATE OF 2 BBL PER MINUTE AT 500#. DISPLACED 50 SX CMT WITH 200# HULLS IN THE LAST 25 SX THROUGH THE PERFORATIONS. CUT CASING AT 900' BUT COULDN'T GET PIPE FREE. PERFORATED AT 560' & ESTABLISHED A PUMP RATE OF 3 1/2 BBL PER MINUTE AT 300#. PUMP 235 SX CMT CIRCULATING 15 SX CMT TO THE PIT.

Perfs:


Top	Bot	Thru	Comments
5113	5115		
5107	5109		
5100	5102		

INVOICED  
JUL 20 2018

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR SENT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed  (TECHNICIAN)

RECEIVED  
MAY - 7 2018  
KCC DODGE CITY

JA