

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-127-20287-00-01
Spot: NENENE Sec/Twnshp/Rge: 15-16S-5E
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: KURTENBACH Well #: 1
County: MORRIS Total Vertical Depth: 2250 feet

Operator License No.: 34792
Op Name: EAGLE ENERGY RESOURCES LLC
Address: 153 S. BROADWAY ST.
LAPORTE, TX 77571

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2250		120 SX
SURF	8.625	180		125 SX

Well Type: SWD UIC Docket No: D19686.0 Date/Time to Plug: 04/20/2018 12:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: JEFF SCOTT Company: Phone: (785) 254-7825

Proposed Plugging Method: AS PER KCC RULES & REGS. USUALLY THIS CONSISTS OF A 50' SAND PLUG AT BOTTOM COVERED WITH A 5 SACK CEMENT PLUG. FILL FROM 250' TO SURFACE WITH CEMENT (ANNULUS AND CASING). CUT CASING OFF BELOW GROUND LEVEL. RESTORE GROUND AS NEEDED.

Plugging Proposal Received By: JERRY SPARLING Witness Type: PARTIAL
Date/Time Plugging Completed: 04/24/2018 11:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

4-20-18 CIBP WAS SET AT 1550' AND TOPPED WITH 2 SX COMMON CEMENT. PERF TECH SET THE CIBP AND TOPPED WITH CEMENT IN BAILER. THEN PERFORATED @ 250'. 4-24-18 PUMPED 100 SX COMMON CEMENT WITH 4% GEL AND 2% CC FROM 250' TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
1545	1550	CSG	

INVOICED
JUL 20 2018

Remarks: DENIED TA - 10 YR WELL

Plugged through: CSG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)