

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21054-00-01

Spot: NENESW

Sec/Twnshp/Rge: 10-30S-34W

2070 feet from S Section Line, 2974 feet from E Section Line

Lease Name: MLP LEATHERSLAND

Well #: 1-10

County: HASKELL

Total Vertical Depth: 5655 feet

Operator License No.: 34434

Op Name: EDISON OPERATING COMPANY LLC

Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5354		WITH 2 SX CMT
PC		2947		WITH 300 SX CMT
PROD	5.5	5679		160 SX
SURF	8.625	1757		WITH 675 SX CMT

Well Type: EOR

UIC Docket No: E28039.4

Date/Time to Plug: 05/08/2018 9:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: BRIAN J MCCOY

Company: BASIC ENERGY SERVICES, LP

Phone: (316) 214-3658

Proposed Plugging Method: SET CIBP @ 5370' WITH 2 SX CMT. PLUG AT 1800' WITH 30 SX CMT. PLUG AT 660' CMT TO 0'. CHECK BACKSIDE WITH CMT TO 300#.

Plugging Proposal Received By: KENNY SULLIVAN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 05/08/2018 11:30 AM

KCC Agent: HEITH WALSH

Actual Plugging Report:

SET CIBP @ 5354' WITH 2 SX CMT. RIH WITH TBG TO 1798'. 1ST PLUG AT 1798' WITH 30 SX CMT. TOOH WITH TBG TO 665'. 2ND PLUG CIRCULATE 55 SX CMT FROM 665' TO 0'. TOOH WITH TBG. TOPPED OFF 5 1/2" CASING WITH 20 SX CMT. PUMPED 5 SX CMT INTO THE 8 5/8" X 5 1/2" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
5418	5482		

INVOICED
JUL 20 2018

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BASIC ENERGY.

Plugged through: TBG

District: 01

Signed

Heith Walsh

(TECHNICIAN)

RECEIVED
MAY 11 2018
KCC DODGE CITY

SA