

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-00589-00-01

Spot: SWSNW

Sec/Twnshp/Rge: 10-26S-8E

2970 feet from S Section Line, 3630 feet from E Section Line

Lease Name: RICE

Well #: 7

County: GREENWOOD

Total Vertical Depth: 2536 feet

Operator License No.: 5697

Op Name: JACKSON BROTHERS, L.L.C.

Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	4.5	2497		50 SX
------	-----	------	--	-------

SURF	9.625	120		80 SX
------	-------	-----	--	-------

Well Type: EOR

UIC Docket No: E22122.1

Date/Time to Plug: 05/08/2018 9:30 AM

Plug Co. License No.: 6112

Plug Co. Name: LONG DRILLING COMPANY, LLC

Proposal Revd. from: ROSCOE G. JACKSON II

Company:

Phone: (620) 583-5122

Proposed Plugging Method: 1. 50-ft. cement plug inside 4.500" casing at 2470-2420 ft. 2. 50-ft. cement plug inside and outside 4.500" at 1230-1180 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: PARTIAL

Date/Time Plugging Completed: 05/08/2018 12:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 2466', pumped 20 sxs cement, pulled tubing to 1200', pumped 20 sxs cement, pulled tubing to 160', pumped 30 sxs cement, to surface, gel spacers between cement plugs.

RECEIVED
KCC DIST #3
MAY 15 2018
CHANUTE, KS

INVOICED

JUL 20 2018

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern
(TECHNICIAN)

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



15-073-00589-000
Cement or Acid Field Report
Ticket No. **3896**
Foreman Rick Ledford
Camp Eureka KS

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
5-8-18	1008	Rice # 7				GW	KS	
Customer <u>Jackson Brothers LLC</u>			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address <u>116 E. 3rd</u>					<u>104</u>	<u>Alan M.</u>		
City <u>Eureka</u>					<u>112</u>	<u>Rick L.</u>		
State <u>KS</u>					<u>145</u>	<u>Rick L.</u>		
Zip Code <u>67045</u>					<u>121</u>	<u>Greg M.</u>		

Job Type P.T.A. old well Hole Depth _____ Slurry Vol. _____ Tubing 2 3/8"
Casing Depth _____ Hole Size _____ Slurry Wt. 14# Drill Pipe _____
Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK 7.0 Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting- Rig up to 2 3/8" tubing. Plugging orders as follows:

20 SKS w/ bulls @ 2420'
10 SKS @ 1180'
40 SKS @ 250' to surface

"Thank You"

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	10	Mileage	3.95	39.50
C203	20 SKS	60/40 Permin cement	12.75	892.50
C206	240"	4% gel	.20	48.00
C206	300"	gel-flush	.20	60.00
C214	40"	bulls	.45	18.00
INVOICED				
C108A	3.01	tax mileage bulk truck	m/c	345.00
JUL 20 2018				
C113	3 hrs	80 GAL VAC. TRK	85.00	255.00
C224	3000 gal.	city water	10.00/1000	30.00
590 (131.05) # 8489.80				
Subtotal				2438.00
Sales Tax				182.85
Authorization _____ Title _____				Total 2620.85

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.