

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22135-00-01
Spot: SWNESE Sec/Twnshp/Rge: 14-24S-15W
2032 feet from S Section Line, 336 feet from E Section Line
Lease Name: ENGLISH-REID SUITER Well #: 2-1
County: STAFFORD Total Vertical Depth: 4355 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, LL
Address: PO BOX 164
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4355	0	WITH 150 SX CMT
SURF	8.625	511		WITH 350 SX CMT

Well Type: EOR UIC Docket No: E19845.3 Date/Time to Plug: 04/24/2018 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: PRESTON DREILING Company: NORTHERN LIGHTS OIL CO. Phone: (785) 639-2099

Proposed Plugging Method: LOAD HOLE & PRESSURE TEST CASING. PICK UP TBG & SET BOTTOM PLUG AT 4200' WITH 50 SX CMT & 100# HULLS. PERFORATE AT 1000'. IF CSAING TESTS OK PUMP CMT TO SURFACE FROM 1000'. PLUG THROUGH TBG AT 1000' WITH 25 SX CMT FOLLOWED BY 25 SX CMT WITH 100# HULLS PULL TBG TO 540' & PUMP CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2018 8:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

TIH WITH TBG TO 4220'. PUMP 100 SX CMT WITH 300# HULLS. PULL TBG & WAIT ON CMT TO SET. TIH WITH TBG & TAG PLUG AT 3255'. PRESSURE TEST ON CASING FAILED. POOH WITH TBG. PERFORATE AT 1000' & 540'. TIH WITH TBG. BREAK CIRCULATION WITH WATER THEN PUMP 25 SX CMT FOLLOWED BY 25 SX CMT WITH 100# HULLS. POOH WITH TBG TO 540'. PUMP 185 SX CMT TO SURFACE IN & OUTSIDE 5 1/2" CASING. PULL TBG OUT OF HOLE & TOP OFF CASING & BACKSIDE WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4277	4285		

INVOICED


JUL 20 2018

Remarks: COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
MAY - 1 2018
KCC DODGE CITY