

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-22015-00-00  
Spot: SESESWSE Sec/Twnshp/Rge: 4-35S-8W  
200 feet from S Section Line, 1490 feet from E Section Line  
Lease Name: SHAYNE SWD 3508 Well #: 1-4  
County: HARPER Total Vertical Depth: 6042 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| COND   | 20   | 79         |             | 10 SX    |
| I1     | 5.5  | 5664       |             | 675 SX   |
| PROD   | 5.5  | 5664       |             | 675 SX   |
| SURF   | 8.63 | 747        |             | 430 SX   |
| T1     | 3.5  | 5619       |             |          |

Well Type: SWD UIC Docket No: D31834.0 Date/Time to Plug: 05/02/2018 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-6532

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 05/02/2018 6:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TIH WITH CIBP ON 2 3/8" TUBING. SET AND RELEASED CIBP AT 5600'.  
CIRCULATED 130 BBLs OF MUD & SPOTTED 25 SX CEMENT. TOH WITH TUBING.  
CUT & REMOVE 1228' OF 5 1/2" CASING. TIH WITH TUBING TO 1200' AND SPOT 50  
SX CEMENT. PULL TUBING TO 800' AND SPOT 50 SX CEMENT. PULL TUBING TO  
300' AND CIRCULATE CEMENT TO SURFACE USING 85 SX CEMENT.

Perfs:

INVOICED  
JUL 20 2018

Remarks: ORR ENTERPRISES. CLASS C CEMENT. FAILED MIT

Plugged through: TBG

District: 02

Signed   
(TECHNICIAN)

*Handwritten mark*