

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-19687-00-00
Spot: NWNESWSW Sec/Twnshp/Rgc: 27-29S-15E
1014 feet from S Section Line, 4360 feet from E Section Line
Lease Name: VAN CAMP Well #: 11
County: WILSON Total Vertical Depth: 1225 feet

Operator License No.: 4485
Op Name: VERDE OIL COMPANY
Address: 7701 BROADWAY ST., STE 200
SAN ANTONIO, TX 78209

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1222	924	75 SX
SURF	7	150		50 SX

Well Type: EOR UIC Docket No: E08283.2 Date/Time to Plug: 06/25/2018 9:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Revd. from: JEFF DALE Company: VERDE OIL COMPANY Phone: (620) 754-3800

Proposed Plugging Method: Shoot 4-1/2" casing off @ 890' and recover. Run tubing to PBTD & circulate hole with 40 vis, 9.0 ppg gel. Pump plugs as follows: 20 sacks @ TD, 20 sacks @ 500' & 350' to surface. All cement will be Class A Neat. Cut off casing strings below plow depth & restore location.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 06/25/2018 9:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

According to operator, 924 ft of the 4.5 inch casing was shot off and recovered. A cement string was then lowered to 1210 feet and circulation established with 40 viscosity gel. A 20 sack cement plug was placed at TD. The cement string was pulled to 550 feet and a 20 sack plug placed. The cement string was pulled to 250 feet and the well filled to top with cement. A total of 99 sacks of Class A Neat cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1161	1196		

RECEIVED
KCC DIST # 3
JUL 19 2018
CHANUTE, KS
AD

INVOICED
JUL 24 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)