

15.009.14397.0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barton County, Sec. 8 Twp. 20 Rge. 11 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
C S/2 SW NW


Lease Owner Kaiser-Francis Oil Company  
Lease Name Duncan B Well No. 1  
Office Address Box 666, Ellinwood, Kansas 67526  
Character of Well (Completed as Oil, Gas or Dry Hole) oil

Date Well completed April 5 1940  
Application for plugging filed October 5 1978  
Application for plugging approved 19  
Plugging commenced November 3 1978  
Plugging completed November 14 1978  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3322'  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
			197'	10 3/4"	197'	none
			3304'	5 1/2"	3304'	159.17

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pushed plug to 2780' with 20' of sand and dumped 5 sacks of cement.

Sun Cementing Inc. plugged well pumping in 3 sacks of hulls, 10 sacks of gel and 125 sacks of cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor PIPE PULLERS, INC.  
BOX 128, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON, ss.  
Evelyn Roth (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth  
Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of November, 1978

My commission expires



Jenny Kasselmann  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

11-21-78

NOV 21 1978  
CONSERVATION DIVISION  
Wichita, Kansas

DUNCAN "B" WELL NO. I

Center of S/2 SW/4 NW/4 8-20-11W, Barton County, Kansas  
 Operator: Simpson Oil Co., and Alpine Oil & Royalty Co., Inc.  
 Contractor: Simpson & Noble, Inc.  
 Commenced: March 8, 1940  
 Completed: April 5, 1940  
 Rotary and Completed with Cable Tools

Potential: 2057  
 Total Depth 3322  
 Acidized

LOG

Sand and gravel	103
Blue Shale	215
(10 3/4" Casing at 198')	
Red Bed	540
Anhydrite	570
Red Bed	718
Shale and Shells	1060
Salt and Shale	1235
Shale and Shells	1408
Lime and Shale Breaks	1556
Broken Lime	2112
Shale and Shells	2415
Broken Lime and Shale	2529
Broken Lime	2779
Lime	2907
Broken Lime	2956
Lime	2980
Shale and Shells	3026
Lime (K.C.)	3060
Lime	3124
Broken Lime	3295
Lime	3306
Lime (Arbuckle)	3308
(5 1/2" Casing)	
Lime, Total Depth	3322

RECEIVED  
 STATE CORPORATION COMMISSION

OCT - 6 1978

CONSERVATION DIVISION  
 Wichita, Kansas

Sample Tops

Elevation	1781
Anhydrite (Driller's)	540
Topeka	2670
Lansing	3060
Arbuckle	3304