

STATE OF KANSAS
OIL AND GAS COMMISSION
D. S. Market, Room 2078
Wichita, KS 67202
APR 30 2003

WELL PLUGGING RECORD
K.A.R.-82-3-117
15,009.23467.0000

API NUMBER 15-009-23,067-000

LEASE NAME Peters

WELL NUMBER 1

3400 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 8 TWP. 20SRGE. 11W (E) or (W)

COUNTY Barton

Date Well Completed

Plugging Commenced 4-18-03

Plugging Completed 4-21-03

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd. St. North #300 Wichita, Ks. 67226

PHONE (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well Oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jay Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3309'

How depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	248'	None
				4-1/2"	3307'	1600'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from _____ feet to _____ feet each section.
Plugged off bottom with sand to 3250' and 4 sacks cement. Cuttpipe @1800', 1700' and 1600'.
Pulled casing up to 1300', pumped 90 sacks cement with 300# hulls, pulled up to 500 ft and pumped 30 sacks cement with 100# hulls, pulled up to 250' and circulated 70 sacks cement to surface. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 29th day of April, 2003

Irene Herzberg
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05

Form CP
Revised 05-