

15.009.14390.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Howard

WELL NUMBER #1

2310 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 8 TWP. 20S RGE. 11W (S) (W)

COUNTY Barton

Date Well Completed 2-11-40

Plugging Commenced 1-2-91

Plugging Completed 1-11-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mustang Oil & Gas Corporation

ADDRESS P.O. Box 1609, Great Bend, Kansas 67530

PHONE#(316) 792-7323 OPERATORS LICENSE NO. 5652

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-2-91 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3306 Bottom 3320 T.D. 3320

Show depth and thickness of all water, oil and gas formations.

3-25-91

RECEIVED
STATE CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil & water	3306	20	9 5/8	234'	none
				5 1/2	3306	none

MAR 25 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf 4 holes @ 550', Run 2 7/8" tubing to 3115'. Allied mixed 100 sxs 65/35 poz w/ 10% gel w/ 100 lbs hulls. Pulled 33 its tubing to 2000'. Spot 100 sxs 65/35 poz. Pulled 33 its tubing to 1000'. Spot 125 sxs 65/35 poz. Cement circulated to surface. Lay down tubing. Perforate 4 holes @ 17' and pump 76 sxs 65/35 poz. On 1-11-91 run wireline to 72'. Mix 25 sxs 65/35 poz

(If additional description is necessary, use BACK of this form.)

w/ 100 lbs hulls, fill cement to surface.

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Box 31, Russell, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Mustang Oil & Gas Corporation


STATE OF Kansas COUNTY OF Barton, ss.

J.P. Meroney (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) J.P. Meroney

(Address) P.O. Box 1609, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 91



Pamela K. Walters

Notary Public Pamela K. Walters

My Commission Expires August 25, 1991