


Give All Information Completely
Make Required Affidavit
Mail or Deliver Rep. to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton

County. Sec. 8 Twp. 20S Rge. 11W (X) (W)

Location as "NE/CNW/SW" or footage from lines CS/2 NW SW 8-20-11W

Lease Owner Degen Pipe and Supply Co.

Lease Name Howard Well No. 3

Office Address Box 107-Red Fork Station - Tulsa, Okla.

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved August 20 19 58

Plugging commenced August 23 19 58

Plugging completed September 2 19 58

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Truin

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back 10' in pipe with gravel. Dumped 5 sacks of cement. Shot pipe off at 2269'. Pulled pipe and mudded hole to 130'. Set rock bridge and dumped 25 sacks of cement. Finished mudding to 40'. Set rock bridge and dumped 10 sacks of cement at base of cellar.

9-11-58
RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

Address

STATE OF Kans. COUNTY OF Reno, ss.

Employee (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

R. R. #4

(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of Sept. 19 58

August 12, 1961

My commission expires

Notary Public.



PLUGGING

FILE SEC 8 T. 20 R. 11W
BOOK PAGE 124 LINE 7

15.009.19526.0000

Well Log of E. Howard #3

Date spudded: July 9, 1940

Loc: Sec. 8-20-11

Date set casing: July 19, 1940

Barton County, Kansas

Date completed: July 27, 1940

Gulf Oil Corporation

Total depth: 3290'

From	To	Formation	Remarks
0	50	Sand	
50	100	Shale & lime	
100	238	Shale & shells	
238	680	Shale & shells	
680	1040	Shale & shells	
1040	1085	Salt	
1085	1200	Salt	
1200	1338	Shale & shells	
1338	1410	Shale & shells	
1410	1480	Lime	
1480	1630	Lime	
1630	1640	Lime	
1640	1720	Lime	
1720	1820	Lime & shale	
1820	1940	Lime & shale	
1940	2040	Shale & lime	
2040	2125	Shale & lime	
2125	2215	Shale & shells	
2215	2315	Lime & shale	
2315	2420	Shale & lime	
2420	2500	Lime & shale	
2500	2572	Shale & lime	
2572	2632	Shale & lime	
2632	2735	Lime & shale	
2735	2800	Lime & shale	
2800	2840	Lime	
2840	2920	Lime	
2920	2940	Lime	
2940	3010	Shale	
3010	3030	Shale	
3030	3066	Shale & lime	
3066	3140	Lime	
3140	3195	Shale & lime	
3195	3225	Shale & lime	
3225	3270	Lime	
3270	3287	Lime	
3287	3290	Lime	

Subscribed and sworn to before me this 30th
day of July, 1940.

W. L. Sarnon
Notary Public

My commission expires Aug. 30, 1945

I hereby certify the foregoing to be
a true and correct copy of the original driller's
log of the E. Howard #3.

Colene Little

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1958

PLUGGING
FILE SEC 8 T 20 R 11
BOOK PAGE 124 LINE 7

CONSERVATION DIVISION
Wichita, Kansas