

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Inquiries Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Barton

County: Sec. 8 Twp. 20 Rge. 11 (E) (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C-S/2 SW/4 NE/4
Lease Owner Simpson Oil Company
Lease Name Andreae Well No. 1
Office Address 713 First Nat'l. Bldg., Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole
Date, well completed 2-3 193 40
Application for plugging filed 2-3 193 40
Application for plugging approved 2-3 193 40
Plugging Commenced 2-3 193 40
Plugging Completed 2-3 193 40
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production.....193.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Agent who supervised plugging of this well. Alexander
Producing formation. — Depth to top. 00 Bottom. 3395 Total Depth of Well. 3395 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS



CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 180 to 195 feet to 15' feet for each plug set.

Well was filled with rotary mud from 195' to 3395', cement plug from 180' to 195' filled with rotary mud from 180' to 20', cement from 5' to 20'

2-10-40



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Simpson Oil Company
Address 713 First Nat'l Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

Sam Payne Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James A. [illegible]

713 First Nat'l. Bldg, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 8th day of February 19 40

My commission expires March 30, 1940

17-6058 10-88-5M

.....
Notary Public.

ANDREAE WELL NO. 1

Simpson Oil Company et al.

Contractor: Simpson & Noble, Inc.

Location: Center of South Half of Southwest Quarter of Northeast Quarter 8-20-11W
(C-S/2-SW/4-NE/4) Barton County, Kansas

Commenced: 1-21-40

Production: DRY

Completed: 2-3-40

Total Depth: 3395'

Log

(Figures Indicate Bottom of Formations)

Sand	70
Clay	190
Red bed	522
13" casing @ 195	
Anhydrite	540
Red bed	730
Shale and shells	826
Shale, lime, salt	1230
Shale and lime shells	1514
Lime and shale breaks	2105
Broken lime	2232
Shale and shells	2350
Broken lime	2660
Lime	2843
Broken lime	2980
Shale and lime shells	3062
Top Lansing and Kansas City	3075
Lime	3263
Top Conglomerate	3300
Broken lime and conglomerate	3395
Total Depth	3395

