


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 15 Twp. 20S Rge. 11W (W)
Location as "NE/CNW/SW" or footage from lines W 1/2 NE SW
Lease Owner Tomlinson-Kathol, Inc.
Lease Name Brenn Well No. 6
Office Address 1125 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-27-68 19
Application for plugging filed 2-27-68 19
Application for plugging approved 2-27-68 19
Plugging commenced 2-27-68 19
Plugging completed 2-27-68 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3345 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug set @ 350' cemented with 40 sks. 50/50 Posmix, 6% gel
Plug set @ 220' cemented with 25 sks. 50/50 Posmix, 6% gel
Plug set @ 40' cemented with 1/2 sk. hulls, 10 sks. 50/50 Posmix

RECEIVED
STATE CORPORATION COMMISSION
FEB 29 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of February, 19 68.

My commission expires April 1, 1971

Glanda [Signature]
Notary Public.

DRILLER'S LOG

COMPANY: Tomlinson-Kathol, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: BRENN #6
 LOCATION: W $\frac{1}{2}$ NE SW SECTION 15-20S-11W
 BARTON COUNTY, KANSAS
 COMMENCED: 2-21-68
 COMPLETED: 2-27-68

0	80	Sand, Clay
80	232	Shale, Sand
232	507	Shale
507	540	Anhydrite
540	775	Shale, Shells
775	1055	Redbed, Shale
1055	1370	Shale, Sand
1370	2125	Lime, Shale
2125	2730	Shale, Lime
2730	2845	Lime, Shale
2845	3335	Lime
3335	3345	Arbuckle
	<u>3345</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" 8 rd. 24# used surface casing set @ 232' cemented with 250 sacks. Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Brenn #6 Well, W $\frac{1}{2}$ NE SW of Section 15, Township 20 South, Range 11 West, Barton County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 28th day of February, 1968.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1968 ~~71~~