

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 15 Twp. 20 Rge. 11 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner The Henderson Oil Company

Lease Name Brenn Well No. 2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19__

Application for plugging filed _____ 19__

Application for plugging approved _____ 19__


Plugging commenced 8-10-65 _____ 19__

Plugging completed 8-11-65 _____ 19__

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Gib Lieker

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3308 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	None
				4-1/2"	3304'	1271'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 2525', sanded hole to 2485' and dumped 3 sacks of cement with dump bailer. Pulled 4 1/2" casing, bailed hole to 300', set rock bridge to 290' and dumped 20 sacks of cement at 290'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

8-20-65

RECEIVED
STATE CORPORATION COMMISSION

AUG 20 1965

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight

(employee of owner) or (owner/lessee) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 65

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1965

CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

The Henderson Oil Company et al - owners - Brem #2
SW SW SW Section 15-20-11W
Barton County, Kansas

Elevation 1770 R.B.

Tops at Rotary Bushing

Topeka 2646
Heebner 2913
Brown Lime 3040
Lansing 3058
Arbuckle 3303

Figures Indicate Bottom of Formation

0 - 100 Sand and gravel
155 Shale
185 Sand and gravel
505 Red bed and shells
530 Anhydrite
1450 Shale and lime
1570 Lime
2050 Lime and shale
2765 Shale and lime
2920 Lime
3020 Lime and shale
3306 Lime
3306 Rotary T. D.

Pipe Record:

8 5/8" set at 320'
4 1/2" set at 3304'

Rotary Commenced: Sept 23, 1950
Rotary Completed: Oct. 2, 1950

Cable Tools Commenced Oct. 6, 1950
Cable Tools Completed Oct 14, 1950

Cable Tool Work:

3306 -03 Lime
2000 gal acid

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

I, J. A. Henderson, Secretary of The Henderson Oil Company, part owner of the above described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements, and matters herein contained pertaining to the log of the above described well, and that the same are true and correct.

J. A. Henderson

Sworn and subscribed to before me this 16th day of October, 1950.

Ina Swanson
NOTARY PUBLIC

My commission expires April 28, 1954.