

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely.  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton County, Sec. 15 Twp. 20 Rge. 11 (X) (W)

Location as "NE/CNWSW" or footage from lines SE-SW-NE

Lease Owner C. E. Ash Et al

Lease Name Minnie Jutting "A" Well No. 1

Office Address 309 Petroleum Bldg. Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 1-8 1957

Application for plugging filed 1-8 1957

Application for plugging approved 1-8 1957


Plugging commenced 1-8 1957

Plugging completed 1-8 1957

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Arbuckle Lime Depth to top 3355 Bottom 3374 Total Depth of Well 3374 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Water	3355	3374	8 5/8	225'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded with Heavy Rotary mud 3374' up 210'  
Set plug at 210' with Rock & 2 sax cotton seed hulls, 20 sacks cement  
Mudded from 210' up to 35' set plug at 35' rock & hulls and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor BEA Drilling Co.

Address P.O. Box 211, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
C. E. ASH (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. Ash

309 Petroleum Bldg., Wichita 2, Kans.

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of January, 19 57

My commission expires March 11, 1957

D.S. G. [Signature] Notary Public.  
RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING  
FILE SEC 15 T. 20 R. 11W  
BOOK PAGE 132 LINE 24

1-11-57  
CONSERVATION DIVISION  
Wichita, Kansas

C. E. ASH Et al

Minnie Jutting "A" #1  
 SE-SW-NE Sec 15-20-11  
 Barton County, Kansas

Comm Rig up: 12-18-56	Elevation Gr: 1764'
Comm Drlg. : 12-20-56	Elevation DF: 1767'
Comp R.D : 1- 8-57	Elevation RB: 1769'
Completed : 1- 8-57	Initial Prod: DRY
Total Depth: 3374'	Contractor : BEA Drlg. Co.
	Tools : Rotary

CASING RECORD

<u>Run</u>	<u>Pulled</u>	<u>Left In</u>
225' 8-5/8" 24# J-55 Smls Cemented with 125 sacks cement	None	225' Surface

STRATA	DEPTH	FORMATION TOPS RB 3' Above Derrick Floor
Sand	75	Heebner Shale 2922 (-1153)
Blue Shale	185	Brown Lime 3049 (-1280)
Red Rock	515	Lansing KC 3065 (-1296)
Anhydrite	530	Conglomerate 3320 (-1551)
Slate & Shells	1020	Arbuckle Lime 3355 (-1586)
Salt & Shale	1205	
Shale & Shells	1420	Lansing Show of Oil 3162'
Lime & Shale	3050	
Lime	3298	DST 3150-3162 Open 48 Minutes
Lime & Shale	3320	Rec 20' Mud
Lime & Cong.	3374	BHP 1020#
Total Depth	3374	

D & A

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

\_\_\_\_\_  
 C. E. ASH

STATE OF KANSAS )  
 COUNTY OF SEDGWICK ) SS:

Subscribed and sworn to before me this 10th day of January, 1957.

\_\_\_\_\_  
 D. S. Goforth Notary Public

My commission expires March 11, 1957

PLUGGING  
 FILE SEC 15 T. 20 R. 11 W  
 BOOK PAGE 132 LINE 24

RECEIVED  
 STATE CORPORATION COMMISSION

JAN 11 1957

CONSERVATION DIVISION  
 Wichita, Kansas