

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 5 Twp. 19S Rge. ~~XXX~~ 1 (W)

Location as "NE/CNW%SW%" or footage from lines NW NE NW

Lease Owner Murfin Drilling Co. - Raymond Oil Co.

Lease Name Sadey Well No. 1

Office Address 617 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 27 19 58

Application for plugging filed September 27 19 58

Application for plugging approved September 27 19 58

Plugging commenced September 27 19 58

Plugging completed September 27 19 58

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert, Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3025 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	190'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug at 180' with 1/4 sx. hulls. Displaced 20 sxs. cement.

Set 2nd plug at 35' with 1/4 sx. hulls. Displaced 10 sxs. cement.

Bridged rat hole. Displaced 2 sxs. cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Company

Address 617 Union Center, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. W. R. Murfin

(employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature] 617 Union Center, Wichita 2, Kansas

SUBSCRIBED AND SWORN TO before me this 7th day of October 19 58.

My commission expires March 23, 1960

Donna M. Matzek Notary Public.

PLUGGING CONSERVATION DIVISION
FILE SEC 5 T 19 R 10
BOOK PAGE 134 LINE 20


OCT 8 1958
Wichita, Kansas 10-8-58

WELL LOG

COMPANY **Murfin Drilling Company - Raymond Oil Co.** SEC. 5 T. 19S R. 1W
FARM **Sadey** NO. 1 LOC. NW NE NW

TOTAL DEPTH **3025'**
COMM. **9-19-58** COMP. **9-27-58**

COUNTY **McPherson**
KANSAS



SHOT OR TREATED
CONTRACTOR **Murfin Drilling Company**
ISSUED

CASING

20 10
15 8 5/8" @ 190' w/150 SXS.
12 6
13 5

ELEVATION **1587' K.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

190 Shale - Sand
450 Shale & Shells
1265 Shale - Lime
1635 Shells - Shale
2370 Lime - nShale
2665 Lime
2986 Shale - Lime
3025 Miss. Lime

TOPS:

Lansing 2372
Base/Kansas City 2897
Mississippi 2986

PLUGGING
FILE SEC 5 T. 19 R. 1W
BOOK PAGE 134 LINE 20

OCT 8 1958

State of Kansas
County of Sadgwick

ss:

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Sadey #1 well.

W. R. Murfin

Subscribed and sworn to before me this 7th day of October 19 58.

My Commission Expires: March 23, 1960

Donna M. Matzek
NOTARY PUBLIC

Donna M. Matzek