


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 7 Twp. 16 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW NE
Lease Owner Morris & Morris Oil Oper.
Lease Name Hoffman Well No. 7
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed May 2 19 41
Application for plugging filed Aug 28 19 65
Application for plugging approved Aug 30 19 65
Plugging commenced Aug. 30 19 65
Plugging completed Sept. 3 19 65
Reason for abandonment of well or producing formation Production depleted

If a producing well is abandoned, date of last production March 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truan
Producing formation Arbuckle Depth to top 3357 Bottom 3365 Total Depth of Well 3365 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle Lime	oil	3357	3365	13"	201'	0
				8 5/8"	3361'	900'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3365 feet to surface feet for each plug set.

Sanded up to 3000' dump 5 sacks of cement on bottom. Pulled pipe from hole set rock bridge at 200' dump 7 Yds. of concret in hole.
Well completed.

RECEIVED
STATE CORPORATION COMMISSION

OCT 20 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Pipe Pulling Co.
Address P.O. Box 313 Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Bill Morris III (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill Morris III

Box 511, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of October, 1965

My commission expires March 9, 1966

Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

COPY

SINCLAIR PRAIRIE OIL CO.
Louis Hoffman No. 7

SEC. 7 T. 16 R. 13W.

SE NW NE

990' FN 990' F W. lines NE $\frac{1}{4}$

15-009-03448-00-00

County Barton.

Total Depth. 3364 $\frac{1}{2}$

Comm. 5-7-41 Comp. 5-22-41

Shot or Treated.

Contractor. Harbar Drilling Co.

Issued. 7-5-41

CASING.

13" 201'

85/8" 3393 $\frac{1}{2}$

2 $\frac{3}{8}$ " tubing.

Elevation.

Production. Pot. 31,189B.

no wtr. drawdown

Allowed Pot. 3000B.

Figures Indicate Bottom of Formations.

shale and sholls	202	
shale	390	
shale and sholls	646	Top of rotary table.
shale sholls red bed	892	
anhydrite	940	
shale and sholls	1345	
salt	1410	
shale and sholls	1600	
shale chert and iron	1720	
shale and limo	1845	
limo	1885	
limo and shale	1966	
limo	2050	
limo and shale	2090	
shale and limo	2260	
limo	2320	
limo and shale	2395	
shale and limo	2465	
shale	2650	
shale and limo	2890	
limo	3053	
shale and limo	3074	
limo broken	3090	
limo	3364 $\frac{1}{2}$	

Total Depth.

Top of Arbucklo 3358 $\frac{1}{2}$ - set 85/8" at 3360'8"
Meas. fr. derrick floor.

T.D. 3364 $\frac{1}{2}$ in Arbucklo.

Fill up 2150' in 2 hours.

no test before acid.

Acidized 1000 gal.

5-28-41 on test by draw down method

made an indicated pot. 31,189 bbls.

oil no water

Top Pot. Allowed for pool is 3000 B.

Surface level to bottom of cellar 4'

Surface level to derrick floor 3'5"

Derrick floor to top of rotary table 1'2"

RECEIVED
STATE CORPORATION COMMISSION
AUG 31 1965
CONSERVATION DIVISION
Wichita, Kansas