

15-009-034 700000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Barton County, Sec. 7 Twp. 16 Rge. 13 (E) (W)

Location as "NE/CNWSW" or footage from lines 330 FWL 330 FSL SE/4
Lease Owner Phillips Petroleum Company
Lease Name McClanahan #2 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 8-3-72 19
Application for plugging approved 8-4-72 19
Plugging commenced 8/21/72 19
Plugging completed 8/26/72 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Truman
Producing formation Depth to top Bottom Total Depth of Well 3349 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 10-3/4 | 640 | none |
| | | | | 7" | 3349 | 1831' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, found T.D. 3170', banded from 3170 to 2930', ran 6 sacks of cement from 2930 to 2900'. Loaded hole, shot pipe at 2553', 2443', 2354', 1875', pulled 62 joints of 7" casing. Set 10' rock bridge at 400', plugged as follows: 3170 to 2930' sand, 2930 to 2900' 6 sacks of cement, 2900 to 400' mud and fluid, 400 to 379' rock bridge, 379 to 0 9 yards ready mix.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1972

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND Sworn to before me this 11th day of September, 1972



MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

My commission expires

Margaret Melcher
Notary Public.

Formation Record

15-009-03470-000

Lease V. McClanahan

Well No. 2

| FROM | TO | KIND | HARDNESS | COLOR | REMARKS |
|------|------|---------------------------|----------|-------|---------|
| 0 | 40 | Surface | | | |
| 40 | 95 | Sand Rock Shells | | | |
| 95 | 300 | Shale & Shells | | | |
| 300 | 395 | Red Bed Shells | | | |
| 395 | 410 | Shale & Shells | | | |
| 410 | 535 | Shale & Pyrite Iron | | | |
| 535 | 565 | Shale & Shells | | | |
| 565 | 590 | Red Sandy Shale | | | |
| 590 | 885 | Shale & Shells | | | |
| 885 | 925 | Anhydrite | | | |
| 925 | 1120 | Shale & Shells | | | |
| 1120 | 1155 | Blue Shale, Sticky | | | |
| 1155 | 1400 | Shale & Shells | | | |
| 1400 | 1540 | Salt, Shale & Shells | | | |
| 1540 | 1645 | Shale & Lime | | | |
| 1645 | 1745 | Hard Lime | | | |
| 1745 | 1870 | Broken Lime | | | |
| 1870 | 2130 | Lime | | | |
| 2130 | 2225 | Broken Lime | | | |
| 2225 | 2335 | Lime & Shale | | | |
| 2335 | 2810 | Lime & Shale | | | |
| 2810 | 2925 | Lime | | | |
| 2925 | 2945 | Lime & Chert | | | |
| 2945 | 3075 | Lime | | | |
| 3075 | 3120 | Lime & Shale | | | |
| 3120 | 3350 | Lime | | | |
| 3350 | 3364 | Lime -- T. D. Cable Tools | | | |

Top of Siliceous ---- 3349'

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1972

CONSERVATION DIVISION
Wichita, Kansas