

15 009-14210000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Barton County, Sec. 7 Twp. 16 Rge. 13 (E) (W)
825' FSL 825' FWL SE/4

Location as "NE/CNWSW4" or footage from lines
Lease Owner Phillips Petroleum Company
Lease Name McClanahan #7 Well No.
Office Address Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 8-3-72 19
Application for plugging approved 8-4-72 19
Plugging commenced 8/29/72 19
Plugging completed 9/6/72 19
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Truman
Producing formation Depth to top Bottom Total Depth of Well 3366 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4	593	none
				7"	3354	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3330', 3330 to 3305' cement 5 sacks.
Loaded hole, set 10' rock bridge at 611', had welder cut off 7".
Plugged as follows: From T.D. to 3330' sand, 3330 to 3305' 5 sacks
of cement, 3305 to 611' mud and fluid, 611 to 591' rock, 591 to 0
6 yards ready mix.

PLUGGING COMPLETE.

9-13-72

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1972

CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS

Subscribed and Sworn to before me this 11th day of September, 1972



Margaret Melcher
Notary Public.

Formation Record

15-009-14210-0000

Lease McClanahan

Well No. 7

FROM	TO	KIND	HARDNESS	COLOR	REMARKS
0	80	Surface sand & shells			
80	593	Shale - Sand & Shells			
593	695	Red beds & Shale			
695	875	Red beds & shells			
875	900	Anhydrite			
900	1345	Shale & shells			
1345	1550	Salt & Lime Shells			
1550	2035	Shale & Lime			
2035	2180	Lime			
2180	2240	Broken Lime			
2240	2335	Broken lime & shale			
2335	2510	Shale			
2510	2650	Lime & shale			
2650	2730	Shale & Lime shells			
2730	2790	Lime			
2790	2813	Shale			
2813	2850	Lime & shale			
2850	2892	Lime			
2892	2900	Shale			
2900	2965	Lime			
2965	3050	Broken Lime & shale			
3030	3065	Lime			
3065	3275	Lime & shale			
3275	3366	Lime			
3366		Total Depth.			Top Arbuckle - 3354'

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1972

CONSERVATION DIVISION
Wichita, Kansas